

NORMAN STREET BRIDGE AND JACARANDA STREET EXTENSION

JULY 2013

STUDY OUTCOMES

STAGE 1



An interim "Stage 1" approach was identified in the Study where the new bridge and roadworks could be constructed in the shorter term connecting Downs Street and Chermiside Road. Jacaranda Street would remain as a two lane road.

Stage 1 works would require the "Five Ways" to be reconfigured to a "Four Ways" to ensure it can operate safely and effectively.

Traffic signals would also be installed at the intersection of Brisbane Road and Dudleigh Street and a roundabout at the intersection of Wattle Street and Dudleigh Street.



Indicative layout of a reconfigured Five Ways

